



ICAR-Central Inland Fisheries Research Institute
Barrackpore, Kolkata -700 120, West Bengal
Phone no. (033) 2592 1190/1191
E-mail : director .cifri @ g mail.com Website :www.cifri.res.in



No.9/9/ RS(TGH)/BKP/17

Date : 15.02.2017

Short Notice for inviting quotation

Sealed limited quotations are invited on behalf of Director, ICAR- Central Inland Fisheries Research Institute, Barrackpore from Registered/Govt.enlisted Contractors (civil works) for the following works

A. Fabrication of shed and ancillary work on the roof of Bio-diversity laboratory at Teesta Guest house, ICAR-CIFRI, Barrackpore.

The estimated cost of the job is A. Rs. 4,88,945/-

Contractor must quote his rates in item wise as specified in the work schedule (Annexure-I) and his signature & seal , after physically ascertaining the site and measurement.

Rs. 12,000 /- (Rupees twelve thousand only) should be enclosed with the quotation in the form of Demand Draft in favour of **ICAR-UNIT, CIFRI** payabale at SBI, Barrackpore (Branch code : 0029) as EMD (Earnest Money Deposit) .

The last date of receiving quotation is 02.03.2017 (till 1 pm) and the quotations will be opened on the same day at 3 PM.

The Director, ICAR-CIFRI, Barrackpore, Kolkata-700 120 reserves the right to accept/reject any quotation or part thereof without assignment any reason.

The scope of the work and description of the items along with terms & conditions of the quotation/(Annexure-II) are available on the CIFRI website i.e. www.cifri.res.in

HEAD OF OFFICE

DETAILS

1. Name of the contractor :
2. Full address :
3. a) Phone No. :
b) Fax No. :
c) Mobile No. :
d) Pan No. :
4. E.M.D. details : Rs..... dated.....
Issuing Bank.....
Branch.....
5. Rate Quoted = :
6. Whether valid Govt. enlisted contractor : Yes/No.
7. List of documents produced : a).....
b).....
c).....
d).....

.....
Signature with date & seal

ANNEXURE-I

Name of the work : Fabrication of shed and ancillary work on the roof of Bio-diversity laboratory
at Teesta Guest house , ICAR-CIFRI, Barrackpore.

Sl.No.	Description of work	Unit	Qty.	Rate quote
1.	Removal of tarfelt from roof and cleaning on the surface same and lead upto 50 m	Sqm	131	
2.	Fully removal of spoiled/concrete and cleaning of the same by means of hacking scrapping, chipping by manually or any other suitable means including disposal of rubbish as per direction of Engineer-in-charge and lead upto 50 m	Sqm	83.5	
3.	Demolishing brick work manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.			
	In cement mortar	Cum	0.2	
4.	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttress, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :			
	1:1.5 : 3(1 Cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	1.5	
5.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.			
	Cold twisted bars	Kg.	125	
6.	Centering and shuttering including strutting, propping etc. and removal of from for :			
	Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	1.5	
7.	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (Thickness to be specified by the manufacturer) , of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved	Sqm	2	

	by Engineer-in-charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 Cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm. Including pointing in white cement mixed with pigment of matching shade complete.			
8.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc. including cutting, hoisting , fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.			
	Hot finished welded type tubes	Kg	1800	
9.	Providing & fixing precoated galvanized iron profile (size, shape and pitch of corrugated as approved by Engineer –in-charge) 0.50 mm (+ 0..05%) total coated thickness with zinc coating 120 grms per sqm as per IS : 277, in 240 mpa steel grade, 5-7 microns. Epoxy primer on both side of the sheet and polyester top coat 15-18 microns . Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-Charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5 X 55 mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces , excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	Sqm	110	
10.	Providing flat iron brackets 50X3 mm size with necessary bolts, nuts and washers etc. for fixing asbestos cement/G.S. sheets gutters with purlins.	Metre	95	
11.	Providing and fixing precoated galvanized steel sheet roofing accessories 0.50 mm (+ 0.05%) total coated thickness , Zinc coating 120 grams per sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyster top coat 15-18 microns using self drilling/self tapping screws complete.			
	Gutter (600 mm over all grith)	metre	95	
12.	Providing and fixing on wall face unplastiscised- Rigid PVC rain water pipes conforming to IS : 13592 Type A , including jointing with seal ring conforming to IS : 5382 , leaving 10 mm gap for thermal expansion, i) Single socketed pipes.			

	110 mm diameter	metre	30	
13.	Providing and fixing unplasticised-PVC pipe clip of approved desing to unplasticised-PVC rain water pipes by means of 50X50X50 mm hard wood plugs, screwed with M.S. screws of required length , including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand)			
	110 mm	Each	15	
14.	Painting with synthetic enamel paint of approved brand and manufacture to give and even shade			
	Two or more coats on new work.	Sqm	50	
15.	Repairs to plaster of thickness 12 to 20 mm patches of area 2.5 sqm and under including cutting the patch in proper shape racking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumpling ground within 50m lead . a)With cement mortar 1:4	Sqm	10	
16.	Applying once coat of water thinkable cement primer of approved brand and manufacture on wall surface.			
	White thinnable cement primer	Sqm	60	
17.	Providing and applying while cement based putty of average thickness 1 mm of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	60	
18.	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade :	Sqm	60	

TOTAL Rs.

(Rupees only)

in words

.....

Contractor's seal and signature

TERMS & CONDITIONS

1. The following documents should be included with the quotation :
 - a) Copy of valid enlistment of Govt. department /Local bodies
 - b) Copy of PAN CARD.
 - c) Copies of credentials successfully completed i) two similar works costing not less than the amount of Rs 2 lacs or ii) One similar work costing not less than the amount of Rs. 2.5 lacs performed during last 3 years of Govt. department/ local bodies only.
 - d) Copy of the labour registration or EPF registration.

The documents of Sl. No. a.b.c and d is mandatory/ must for considering the quotation. If documentary evidence of the same are not enclosed, the tender form will be summarily rejected.

2. The site for the work is instantly available for intimation of the work.
3. Last date for receipt of tender is till 1300 hrs. on 02.03.2017 and will be opened on the same day at 15.00 hrs.
4. Time allowed for completing the work will be 15 days.
5. Earnest Money amounting to **Rs. 12,000/-** in the form of demand draft payable at **STATE BANK OF INDIA**, Barrackpore (Branch code 0029) in favour of **“ICAR-UNIT, CIFRI”** must accompany each tender. Any tender not accompanied with the requisite Earnest Money will be rejected . Earnest Money deposit will bear no interest. Unsuccessful bidders will get refund of Earnest Money deposit on demand within 30 days award of work.
6. The contractor whose quotation is accepted , will be required to furnish a security Deposit for due fulfilment of the contract and 5% of total bill amount will be retained as security deposit for 6(six) month. Earnest Money will be adjusted against the amount of security deposit arrived at and if there is a shortfall the same will be further adjusted against the final bill. The security deposit will be released after six month from the date on which completion certificate is given by the Officer-in-Charge , Works, ICAR - CIFRI The security deposit will earn no interest.
7. The Director, CIFRI has the power to accept or reject any or all tenders received Without assigning any reason whatsoever. All tenders in which any of the Prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.

8. Any modification in the work schedule shall be informed to the Institute and Subsequent payment for such works will be made accordingly on the basis of the final measurements on that specific item on the rate quoted.
9. Canvassing in connection with the tenders is strictly prohibited and the quotations Submitted by the contractors who resort to canvassing will be liable to rejection .
10. All rates shall be quote on tender document itself.
11. On acceptances of the tender, the name of the accredited representatives of Contractor who would be responsible for taking instruction from the OIC, Works shall be communicated to the OIC, Works.
12. The rate should be quoted in item wise as specified in the work schedule (Annexure-I)
13. The rate quoted should be inclusive of all taxes.
14. An agreement will be entered into by the contractor with the Director, CIFRI Within 15 days of issuance of work order.
15. The tenderers are advised to stipulate their condition only on the letter forwarding The tender documents. The tenders must note that any condition inserted by the tenderer on the tender documents will not be acceptable and in case any tender contains such insertions or condition, the tenders will be liable to be rejected.
16. Any overwriting/erasing in tender must be authenticated under the seal and Signature of quotationer.
17. Incomplete tenders, tenders received late or those not in compliance with the terms and conditions set forth herein above are liable to be rejected.
18. The quotation will be subject to any further terms and conditions as may be fixed by the Govt. of India/ICAR/Director, CIFRI.
19. The quotation form is non-transferable . Bidder should purpose the tender form in his/her/their own name, quotation forms purchased by one firm cannot be used by another firm. In case it is so done, the quotation will be summarily rejected.
20. Payment to the firm will be made within 30 (thirty) days after satisfactory completion of work receipt of the bill in triplicate. No request for advance payment will be entertained.

21. The envelope containing the quotation should superscribe **“Fabrication of shed and ancillary work on the roof of Biodiversity laboratory at Teesta Guest house ”**It could sent **through** post on the following address so as to reach within the date.

THE ADMINISTRATIVE OFFICER,
ICAR-CENTRAL INLAND FISHERIES RESEARCH INSTITUTE,
BARRACKPORE, KOLKATA- 700 120.
24 PARGANAS (North).

Administrative Officer